



Expense Approval Note Against Budget

Print Date : 04/05/2024

Approval ID	: 112
Approval For	: ACCOUNT
Department Name	: CIVIL ENGINEERING
SUBJECT	: New Boys Hostel

Details :

Purchase and installation of fire fighting system for new boys hostel

		Allocation :- 0
		Allocation :- 0
Particular	Qty.	Required Amount
SITC Of Main Fire Pump Set Capacity 900 LPM HeadSupplying, installing, testing a (Remarks :)	1	70000
SITC Of Auto Panel For Fire Pump With Arragnment with the interlocking with line (Remarks :)	1	5000
Supply and Laying of the cables Supply and Laying of the cables Supply & aying o (Remarks :)	1	4500
SITC Of the Piping Specials- Butterfly Valves suppling, erecting, testing and co (Remarks :)	1	3950
Butterfly Valve 80 mm Dia. (Remarks :)	1	3100
SITC Of the Piping Specials- Non Return Valves Suppling, erecting, testing and c (Remarks :)	1	2150
SITC Of the Piping Specials- Foot Valves Suppling, erecting, testing and commisi (Remarks :)	1	4050
SITC Of the Piping Specials- Air Release Valve Suppling, erecting, testing and c (Remarks :)	1	1100
SITC of MS C Class Pipe Supplying, laying, fixing, testing and commissioning cla (Remarks :)	6	6360
SITC Of the Pressure Switch Supplying, erecting, testing and comissioning 0 to 7 (Remarks :)	1	1600
SITC Of the Pressure Gauge Suppling, erecting, testing and commssioning 0 to 15 (Remarks :)	1	1350
SITC Of Support Fabrication Supply, & fetting of the on site support fabrication (Remarks :)	5	465
SITC Of Miscellaneous Items Supply, & fetting of the on site Cable Tray for powe (Remarks :)	1	3200
SITC Of Miscellaneous Items Supply, & fetting of the on site Cable Tray for powe (Remarks :)	1	3200
SITC of MS C Class Pipe Supplying, laying, fixing, testing and commissioning cla (Remarks :)	110	170500
MS C Class 25 MM Dia pipe. (Remarks :)	30	10500
SITC of Fire Escape Hydrant - Fire Hydrant Valve Supplying, laying, fixing, test (Remarks :)	8	32400
SITC of Fire Escape Hydrant - Fire Hose Box Supplying, laying, fixing, testing a (Remarks :)	8	15600
SITC of Fire Escape Hydrant - RRL Hose Pipe Supplying, laying, fixing, testing a (Remarks :)	8	32400
SITC of Fire Escape Hydrant - Short Branch Pipe Supplying, laying, fixing, testi (Remarks :)	8	9600
SITC of Fire Escape Hydrant - Fire Hose Reel Drum Supplying, laying, fixing, tes (Remarks :)	8	41200
SITC Of the Piping Specials- Ball Valve 25mm Dia. Suppling, erecting, testing an (Remarks :)	8	3600



SITC Of 02 Way Fire Brigade Inlet With, 02 Nos. 63 mm dia male instantaneous ada (Remarks :)	1	4700
SITC Of Support Fabrication Supply, & fetting of the on site support fabrication (Remarks :)	50	4500
SITC of Fire Alarm Control Panel Conventional Supply, erection, testing and comm (Remarks :)	1	7000
SITC of the Manual Call Point Supply,eration, testing & commisioninng of Address (Remarks :)	8	6400
SITC of Electronic Hooters Supply,eration, testing & commisioninng of convention (Remarks :)	8	6400
SITC Of Armoad Cable Supply, eration, testing & commisioninng of 2 Core 1.5 sq.m (Remarks :)	150	15750
SITC of Hardware Material and Miscellaneous Itmes (Remarks :)	1	10000
SITC of Fire Extinguishers ABC Type Capacity 06 KG (Remarks :)	8	14800
SITC of Fire Extinguishers C02 Type Capacity 4.5 KG (Remarks :)	2	7500
TOTAL		502875
GRAND TOTAL		502875

Request to please approve the expense,

Regards,

Mr. BHUSHAN NIKAM
CIVIL ENGINEERING

* Approval Authority *

10022 - Mr. BHUSHAN NIKAM			 10003 - Col. JOY DANIEL			 10006 - Mr. DEEPAK SHELKE		
Creator	RS 502875	02/05/2024 05:51 PM	Approved	RS 502875	03/05/2024 01:17 PM	Pending	RS 0	03/05/2024 01:17 PM